

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22658-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 22-12S-24W
950 feet from S Section Line, 370 feet from W Section Line
Lease Name: WANDA Well #: 1-22
County: TREGO Total Vertical Depth: 4370 feet

\$142.03

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/30/2010 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 04/30/2010 12:00 PM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 1990' w/25 sxs.
2nd. Plug at 1075' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.


Perfs:

5/10/10
2010061088

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed  (TECHNICIAN) CM

RECEIVED

MAY 10 2010

KCC WICHITA

MAY 03 2010