

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-02319-00-00

Spot: SWSESW

Sec/Twnshp/Rge: 12-26S-18E

590 feet from S Section Line, 3765 feet from E Section Line

Lease Name: RATH

Well #: 6

County: ALLEN

Total Vertical Depth: 850 feet

Operator License No.: 5488

Op Name: TWM PRODUCTION CO., A GENERAL

Address: 1150 HWY 39

CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

SURF	8	20		
------	---	----	--	--

PROD	2	850		
------	---	-----	--	--

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/18/2007 10:00 PM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: MICHAEL J. WIMSETT

Company: TWM PRODUCTION

Phone: (620) 431-4137

Proposed
Plugging
Method:

THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed 01/18/2007 2:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" pipe was run into the 2" casing to 750' Cement was pumped into the 1" pipe until cement circulated from the 2" casing at surface. The 1" pipe was removed. 1" pipe was ran into the 2" and 8" annulus to 475'. Cement was pumped into the 1" pipe until cement circulated from the 8" surface casing at surface. The 1" pipe was removed. Displacement was filled from surface.

RECEIVED

KCC Chanute Dist. #3

CPT
by
BH

Perfs:

RECEIVED

MAY 10 2010

KCC WICHITA

Remarks: SPOT LOCATION ESTABLISHED AS NO. 6 (37.79262 N & 095.39160 W)

Plugged through:

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5488Operator: TWM PROD. CO.Name & 1150 HWY. 59Address CHANUTE, KS. 66720AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated: _____

Plugging Contractor: W & W PRODUCTION CO.Lic. # 5491Address: 1150 HWY 39, CHANUTE, KS. 66720Company to plug at: Hour: 10:00 Day: 18 Month: 1 2007Plugging proposal received from: MIKE WIMSETTCompany Name: W & W PRODUCTION CO. Phone: 620-431-4137Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD BEENCEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCHOF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All ☒ Part ☐

TECHNICIAN

None ☐Operations Completed: Hour: 2:00 PM Day: 18 Month: 1 2007Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 750. CEMENT WASPUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 475'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" SURFACECASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROMSURFACE..

RECEIVED

Remarks: (SPOT LOCATION ESTABLISHED AS NO.6) (37.79262 N& 095.39160 W)

MAY 10 2010

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN