

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-02320-00-00

Spot: NESWSW

Sec/Twnshp/Rge: 12-26S-18E

670 feet from S Section Line, 4179 feet from E Section Line

Lease Name: RATH

Well #: 7

County: ALLEN

Total Vertical Depth: 850 feet

Operator License No.: 5488

Op Name: TWM PRODUCTION CO., A GENERAL

Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8	20		
PROD	2	850		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/18/2007 2:00 PM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: MICHEAL J. WIMSETT

Company: W & W PRODUCTION

Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: PARTIAL

Date/Time Plugging Completed 01/18/2007 4:30 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" pipe was run into the 2" casing to 800'. Cement was pumped into the 1" pipe until cement circulated from the 2" casing at surface. The 1" pipe was removed. 1" pipe was run into the 2" and 8" annulus to 500'. Cement was pumped into the 1" pipe until cement circulated from the 8" surface casing at surface. The 1" pipe was removed. Displacement was filled from surface. 189 sacks of cement were pumped into this well.

RECEIVED

MAY 07 2007 CPT
by
DLH
KCC Chanute Dist. #3

5/13/10
2010061103

Remarks: SPOT LOCATION ESTABLISHED AS NO. 7 (37.79291 N & 095.39303 W)

Plugged through:

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

To: STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5488

Operator: TWM PROD. CO.

Name & 1150 HWY. 59

Address CHANUTE, KS. 66720

AB oil well X Gas Well SWD Well/ Input Well D & A

Other well as hereinafter indicated:

Plugging Contractor: W & W PRODUCTION CO. Lic. # 5491

Address: 1150 HWY 39, CHANUTE, KS. 66720

Company to plug at: Hour: 2:00P.M. Day: 18 Month: 1 2007

Plugging proposal received from: MIKE WIMSETT

Company Name: W & W PRODUCTION CO. Phone: 620-431-4137

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD BEEN
CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH
OF THE WELL AS POSSIBLE FULL OF CEMENT.

 Plugging Proposal Received by: CLAYTON P. TITEL
 TECHNICIAN

Plugging attended by Agent: All Part X None

Operations Completed: Hour: 4:30P.M. Day: 18 Month: 1 2007

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 800. CEMENT WAS
PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE
1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 500'. CEMENT
WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" SURFACE
CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM
SURFACE. 189 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (SPOT LOCTION ESTABLISHED AS NO.7) (37.79291 N& 095.39303 W)
 (If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:


 TECHNICIAN

RECEIVED

MAY 10 2010

CC WICHITA