

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20009-00-00  
Spot: SESE Sec/Twnshp/Rge: 16-1S-18W  
729 feet from S Section Line, 1061 feet from E Section Line  
Lease Name: EMMA IMM Well #: 1  
County: PHILLIPS Total Vertical Depth: 3580 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	w/unknown sxs cmt
PROD	4.5	3579	0	w/100 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/04/2010 11:00 AM  
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION  
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed  
Plugging  
Method:

Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/04/2010 3:40 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 2850' - pumped 140 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 1800' - pumped 150 sxs 60/40 pozmix - 4% gel - lost circulation at 100 sxs.  
Pulled tubing to 900' - pumped 60 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.  
Pulled all tubing. Topped off 4 1/2" casing with 35 sxs 60/40 pozmix - 4% gel.  
Hooked to 8 5/8" x 4 1/2" annulus - pumped 15 sxs 60/40 pozmix - 4% gel.  
S.I.P. 100#.

5/19/10  
2010061121

RECEIVED

MAY 17 2010

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #41675.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

W. E. WICKIZER #1 EMMA IMM 16-1-18W  
 C SE SE  
 Contr. CO TOOLS Cty. PHILLIPS  
 Geol. Pool HUFFSTUTTER  
 E. 2163 KB Cm. 9/9/67 Cp. 12/7/67 IP P 50 BOPD  
 LANS MULTI-ZONE


API 15-147-20,009

SMP Tops	Depth	Datum	Csg.
			8" 200 4" 3579/100 SX
HEEB	3336	-1173	DST 3395-3430/1', 50' SLI OCM, FSIP 848#/30"
TOP	3355	-1192	
LANS	3371	-1208	DST 3432-76/1', 130' SLI OCM, FSIP 1079#/30"
TD	3580	-1417	DST 3514-54/1', 15' OIL, 60' OCM FSIP 576#/30"
			PF 8/3538-40, 12/3522-25, 16/ 3461-65, 12/3449-51, 12/3442-45, 12/3423-26, 24/3407-11, A 3000, ALL ZONES, SWB LD & SWB 36 BO/ 8 HRS, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS