

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20178-00-00
Spot: NENESE Sec/Twnshp/Rge: 16-1S-18W
2324 feet from S Section Line, 365 feet from E Section Line
Lease Name: IMM Well #: 3
County: PHILLIPS Total Vertical Depth: 3606 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	w/unknown sxs cmt
PROD	4.5	3590	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2010 9:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
Fish stuck in the hole at 1490'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2010 10:20 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1455' - pumped 130 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Hooked to 4 1/2" casing - squeezed with 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 500#.
8 5/8" checked - had cement to surface.

Perfs:

5/19/10
201006/12

Remarks: ALLIED CEMENTING COMPANY-TICKET #41324.

Plugged through: TBG

RECEIVED
MAY 17 2010
KCC WICHITA

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

MAY 06 2010

