

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21185-00-00
Spot: SWNE Sec/Twnshp/Rge: 6-6S-20W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: MCCLURG Well #: 2
County: ROOKS Total Vertical Depth: 3531 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	334	0	w/130 sxs cmt
PROD	4.5	3529		w/160 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/07/2010 12:00 PM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Casing leak at approximately 1200' - 1300'.
Used mud pump to drill down to 1670'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/07/2010 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1670' - pumped 110 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 840' - pumped 55 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 50 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 4 1/2" annulus - pumped 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3380	3384		
3310	3316		
3270	3275		

5/19/10
201006/121

RECEIVED
MAY 17 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #41367.

KCC WICHITA

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

MAY 10 2010

PETROLEUM MANAGEMENT, INC.
 400 N. WOODLAWN SUITE 201 #2 MCCLURG 6-6-20W
 WICHITA, KS 67208 SW NE NE
 CONTR PIONEER DRG. CO. CTY ROOKS
 GEOL _____ FIELD RAY

E 2114 KB CM 1/25/81 CARD ISSUED 5/28/81 IP P 48 BOPD & WTR
 LANS 3270-3384 OA

+	+
+	+

API 15-163-21,185

SMP	TOPS	DEPTH	DATUM
ANH		1598	+ 516
B ANH		1632	+ 482
TOP		2998	- 884
HEEB		3195	-1081
TOR		3220	-1106
LANS		3238	-1124
B KC		3429	-1315
GRAN		3528	-1414
RTD		3531	-1417

8-5/8" 334/130sx, 4 1/2" 3529/160sx
 NO DST'S
 MICT - CO, PF 3380-84, 3310-16,
 3270-75, AC 2750 GAL, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS