

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-06144-00-01
Spot: S2NWSW Sec/Twnshp/Rge: 16-11S-15W
1650 feet from S Section Line, 4620 feet from E Section Line
Lease Name: WHITSON Well #: 2
County: RUSSELL Total Vertical Depth: 3339 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	526	0	w/unknown sxs cmt
L1	5.5	3329		
L2	4.5	3339		
PROD	7	3221	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/28/2010 10:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: BOB GRANT Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 75 bbls mud.
Squeezed from 521' - 585' w/80 sxs.
Perforate at 1700' - 975' - 500'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/28/2010 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3175' - pumped 75 bbls drilling mud - followed with 75 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1717' - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 972' - pumped 75 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 500' - pumped 150 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 7" casing with 10 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 7" annulus.
Pressured to 200# immediately.

Perfs:

5/19/10
2010061122

Remarks: ALLIED CEMENTING COMPANY-TICKET #33873.

Plugged through: TBG

RECEIVED
MAY 17 2010

KCC WICHITA

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

SUMMIT DRILLING CO

#2 WHITSON

16-11-15W
S2 NW SW

Contr. _____ RUSSELL County

E 1887 Comm. 7-14-47 Comp. 11-14-47 IP 100 BOPD

Tops	Depth	Datum	Casing
ANH	953		15" 450
			8" 2700
TOP	2695		7" 3218
			Bail 4 BOPH @ 3005
LANS	2995		DD 3339
			1 blr OPH
			A/500
			Bail 1½ BOPH: A/4000
			Pmp 6 BOPH
ARB	3329		11¼" 5" lnr
TD	3339		

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS