

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21253-00-00
Spot: SESWNWSW Sec/Twnshp/Rge: 23-8S-27W
1454 feet from S Section Line, 384 feet from W Section Line
Lease Name: TAYLOR Well #: 1-23
County: SHERIDAN Total Vertical Depth: 3975 feet

Operator License No.: 31930
Op Name: BLUE RIDGE PETROLEUM CORPORATI
Address: PO BOX 1913
ENID, OK 73702

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/06/2010 6:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: BLUE RIDGE PETROLEUM CORPO Phone: (580) 242-3732

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 05/06/2010 7:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 2175' w/25 sxs.
2nd. Plug at 1312' w/100 sxs.
3rd. Plug at 271' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

CM

15-179-21253-00-00
5/19/10
2010061123

RECEIVED
MAY 17 2010

KCC WICHITA

MAY 12 2010