

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-27796-00-00
Spot: NENESESE Sec/Twnshp/Rge: 27-30S-16E
1154 feet from S Section Line, 170 feet from E Section Line
Lease Name: HARE Well #: C1
County: WILSON Total Vertical Depth: 895 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| SURF | 7 | 23 | | 8 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/09/2010 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: REX ASHLOCK Company: COLT ENERGY, INC Phone: (620) 365-3111

Proposed Plugging Method: Run cement string to TD and spot cement plugs at selected intervals with gel spacers.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 02/09/2010 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2" cement string was lowered to 891' and 10 sacks of cement were pumped. The cement string was pulled up to 495' and 10 sacks of cement were pumped. Pulled pipe to 251' and then pumped full of cement to surface. All of the pipe was removed and the well topped off with cement. A total of 75 sacks of portland cement were used to plug well.

Perfs:

RECEIVED

AM D

KCC Chanute Dist. #3

5/19/10
201006126

RECEIVED
MAY 17 2010

KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)