

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33723
Name: Paul Bowman Oil Trust
Address 1: 801 Codell Road
Address 2: _____
City: Codell State: Kansas Zip: 67663 + _____
Contact Person: Louis "Don" Bowman or Terrii Bowman
Phone: (785) 435-2286 M-F

API No. 15 - 051-23348-0000
If pre 1967, supply original completion date: April 12, 1983
Spot Description: NE/4 of 11-T14S-R19W
C -NW SE NE Sec. 11 Twp. 14 S. R. 19 East West
3,630 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis County, Kansas
Lease Name: Stadelman Well #: 1

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: N/A Set at: N/A Cemented with: N/A Sacks
Surface Casing Size: 8 5/8" Set at: 768' Cemented with: 325 sacks Sacks
Production Casing Size: 4 1/2" Set at: 3814' Cemented with: 450 sacks Sacks

List (ALL) Perforations and Bridge Plug Sets:

Perforations @ 3460'-3466', 3520'-3524', 3532'-3536', 3556'-3560', & 3821'-3825'
No Bridge Plugs

Elevation: 2190' (G.L. / K.B.) T.D.: 3836' PBTD: N/A Anhydrite Depth: 1465'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: 3100'
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Will Plug Well According to KCC - District #4's Instructions

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Copy of Card attached

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Louis "Don" Bowman
Address: 801 Codell Road City: Codell State: Kansas Zip: 67663 + _____
Phone: (785) 434-2286
Plugging Contractor License #: 99996 Name: Allied Cementing Company, Inc.
Address 1: 24 S. Lincoln Address 2: P.O. Box 31
City: Russell State: Kansas Zip: 67665 + _____
Phone: (785) 483-2627

Proposed Date of Plugging (if known): May, 10, 2010

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: April 26, 2010 Authorized Operator (Agent): Connie Jo Austin
(Signature)

RECEIVED
KANSAS CORPORATION COMMISSION

APR 27 2010

CONSERVATION DIVISION
WICHITA, KS

Handwritten initials

producing

L.G. STEPHENSON & COMPANY, INC. REPLACEMENT CARD 11-14-19W
7701 E. KELLOGG #670 #1 STADELMAN NW SE NE

WICHITA, KS 67207
CONTR DUKE DRILLING CO., INC. CITY ELLIS

GEOLOGICAL FIELD WC (RIDGE HILL WEST DISC)

ELV 2190 KB SPD 1/30/83 CARD ISSUED 4/28/83 IP P 15 BOPD & 145 BWPD
API 15-051-23, 348 LKC 3514-3669 OA
ARB OH 3814-3837
(NEW PAY - ARB OIL)

+	10
+	1

LOG	Tops	Depth/Datum
ANH		1465+ 725
TOP		3186- 996
HEEB		3440-1250
LANS		3489-1299
BKC		3725-1535
ARB		3812-1622
RTD		3836-1646
LTD		3837-1647

8 5/8" 768/325SX, 4 1/2" 3814/450SX
 DST (1) 3500-3520 (LKC) / 60-45-60-45, SB, 1250' GIP, REC 10' OCM, 600' FROTHY OIL, 70' MW; SIP 875-845, FP 56-278#
 DST (2) 3528-3569 (LKC) / 60-45-60-45, SB, 120' GIP, REC 120' O&GCM (25% OIL), 870' SLI OILY GSY CMW; SIP 847-833#, FP 83-486#
 DST (3) 3607-3634 (LKC) / 40-40-60-45, WB INCRG TO GB, 310' GIP, REC 70' OCM (10% OIL), SIP 333-944#, FP 28-28
 DST (4) 3634-3657 (LKC) / 60-45-60-45, SB, 2300' GIP, REC 360' GSY OIL, SIP 347-375#, FP 28-139#
 DST (5) 3661-3695 (LKC) / TIMES NA, WB DIED / 25", REC 10' SLI OCM, SIP 181-194#, FP 28-28#
 INFO RELEASED: 3/28/85 - ADDED DST INFO
 NOTE: INFO RELEASED: 5/12/83 - WAS OIL WELL - TIGHT HOLE (over)

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

RECEIVED
KANSAS CORPORATION COMMISSION

APR 27 2010

CONSERVATION DIVISION
WICHITA, KS

L.G. STEPHENSON & COMPANY, INC. REPLACEMENT CARD 11-14-19W
#1 STADELMAN NW SE NE

DST (6) 3773-3816 (PENN, ARB) / 45-30-45-30, 40' GIP, REC 80' HOCM; SIP 833-694#, FP 44-83#
 DST (7) 3772-3821 (PENN, ARB) / 30-30-30-30, WB, REC 80' OCM; SIP 819-708#, FP 42-56#
 DST (8) 3775-3826 (PENN, ARB) / 30-30-30-30, REC 70' OCM; SIP 812-714#, FP 42-56#
 DST (9) 3774-3832 (PENN, ARB) / 45-45-30, FB THRU-OUT, 60' GIP, REC 240' HOCM; SIP 1182-1168#, FP 83-153#
 DST (10) INTV NA / MISRUN
 DST (11) 3819-3836 (ARB) / 60-45-75-45, WB INCRG TO SB IN 50", 60' GIP, 500' WTRY MCO, (65% OIL, 15% W, 20% M); SIP 1182-1168#, FP 56-222#
 MICT - CO (ARB OH), SWB 1.16 BFPH (48% O), PF (LKC) 3659-69, 3641-47, 3621-26, W/2 SPF, SET PLUG & PKR TO ISOLATE LOWER PF'S, AC 250G, SWB DRY, SET PLUG & PKR TO ISOLATE PF'S (3641-47); SWB 1.5 BFPH (75% O), ONFU 961' OIL & 125' W; SET PLUG & PKR TO ISOLATE PF'S 3621-26, AC 250G; ONFU 12' OIL & 1854' W; SWB 1 BFPH (98% W), SQZ PF'S 3621-26 W/75 SX, AC 1000G OVER REMAINING PF'S, PF (LANS) 3514-19 W/2 SPF, SWB 1.1 BFPH (91% O), T&R, POP, PULL PLUG, P 10 BOPD & 10 BWPD, PROD DECL, OFF PMP, RE-ENTERED 4/4/83; AC (ARB OH) 250G; AC 1000G OVER PF (LKC) 3514-19; SWB ALL ZNS, REC 13 BFPH (50% O), ONFU 525' OIL & 2081' W; T&R, POP, P 15 BO & 145 BWPD, COMMINGLED

OVER



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

PAUL BOWMAN OIL TRUST
801 CODELL RD
CODELL, KS 67663-8500

April 30, 2010

Re: STADELMAN #1
API 15-051-23348-00-00
11-14S-19W, 3630 FSL 990 FEL
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after October 27, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550