

15-063-20107-00-00

KANSAS

Form CP-3
Rev. 6-4-68

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

STATE CORP
RECEIVED
DEC 30 1971
CONSERVATION DIVISION
WICHITA, KANSAS
12-30-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Zerr Well No. 1

Location NE-SW-SE Sec. 17 Twp. 12 Rge. (E) (W) 30

County Gove Total Depth 4000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 11:15 AM Day 27 Month 12 Year 1971

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud, Pulled DP to 1350' and displaced 110 Cu. Ft. cement
thru DP from 1350' to 1025'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. ...*
Well Plugging Supervisor

DATE 1-11-72
INV. NO. 4934-W2