

15-063-20232-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1974
11-15-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Schoendaler 'A' Well No. 1

Location CNE-SW Sec. 28 Twp. 12 Rge. (E) (W) 30

County Gove Total Depth 4476'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 4:30 AM Day 6 Month 11 Year 1975

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement
thru DP from 1225' to 900'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichol
Well Plugging Supervisor

INVOICED

11/15/74
304-W