

15-063-20193-00-00

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
09-04-1973
SEP 4 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company,

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Knapp Well No. A-1

Location CNE-SW Sec. 13 Twp. 12 Rge. (E) (W) 31

County Gove Total Depth 4230'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address Box #352, Russell, Kansas. License No.

Operation Completed: Hour 12:00 H Day 1 Month 9 Year 1973

The above well was plugged as follows:

282'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 110 Cu. Ft. cement
thru DP from 1500' to 1175'. Pulled DP to 300' and displaced 30 Cu. Ft. cement thru
DP from 300' to 225'. Pulled DP, set bridge @ 30' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

FILED
9-4-73
WV. NO. 7866-62

Signed: *A. L. Nichols*
Well Plugging Supervisor