

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,744-0050

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Cities Service Company

Complete Address 800 Sutton Place Bldg, 209 E. William, Wichita, Ks. 67202

Lease Name Colahan "A" Well No. A-36

Location 1575' ESL & 350' FWL of SW Sec. 24 Twp. 11 Rge. 17 (East) West

County Ellis Total Depth 3668'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pioneer Drilling Co., Inc.

Address 308 W. Mill St., Plainville, Ks. 67663 License No. \_\_\_\_\_

Operation Completed: Hour: 12:30PM Day: 18th Month: Dec. Year: 19 81

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8"-814' s.p. cuc. w/500 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem w/heavy mud between all plugs.

1st plug @ 780' w/70 sacks cement

2nd plug @ 300' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

72-21-81

Jan 19, 1982  
8915-W