

15-051-19295-0000

Form CP-3
Rev. 6-4-68

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company
Complete Address Box 553 Russell, Kansas 67665
Lease Name Colahan "C" Well No. 1
Location SW NW SE Sec. 24 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3593'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 4:45 P Day 7 Month 3 Year 1972

The above well was plugged as follows:

Total Depth 3593' 8 5/8 csg set at 1105' cwc 300 sk.
5 1/2 csg set at 3468' cw 150 sk cmt.
Set 5 1/2 wood plug at 3200' -poured 10' sd- Dumped 5 sk cmt W/dump bailer. (3155-3200)
Cutoff and recovered 2335' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls. Hole in 8 5/8 csg. (1-26-72)
Ran tubing to 525' -displaced 40 sk Halco-Light Cmt.
Pulled tubing to 100' -circ. 20 sk Halco-Light cmt to surface.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: Ken J. Massey
Well Plugging Supervisor

DATE 3-10-72

INV. NO. 5321-10