

15-051-05557-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Colahan "C" Well No. 7

Location C/ E/2 NE SE Sec. 24 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3360'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 9:30 A Day 17 Month 4 Year 1971

The above well was plugged as follows:

Total Depth 3360' 8 5/8 csg set at 1017' cwc

5 1/2 csg set at 3358' cw 100 sk cmt.

~~\_\_\_\_\_~~

2 1/2" tubing stuck on bottom -could not break circulation with Halib. pump truck.

Found Freepoint at 1800' and backedoff, recovering 1800' of 2 1/2" tubing.

Set 5 1/2" wood plug at 1800' -poured 20' sd and dumped 5 sk cmt w/dump bailer.

Recovered 1720' of 5 1/2" csg.

End to 1800' -set rock & sd bridge to 375 -dumped 6 yds R-mix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo R. Murray  
Well Plugging Supervisor

CASH 4/20/71  
INV. NO. 3575-41