

15-051-03426-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1971  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Colahan "A" Well No. 15

Location NW SW SW Sec. 24 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3665'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 5:30 P Day 28 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3665' 8 5/8 csg set at 1110' cwc 335 sk.

5 1/2 csg set at 3665' cw 125 sk cmt.

5 1/2 csg FBTD. 3565 and perf. (3555-3563)

Filled 5 1/2 csg W/sd (3520-3565) dumped 5 sk cmt W/dump bailer. (3475-3520)

Recovered 1280' of 5 1/2 csg.

Pumped down 8 5/8 csg with 60 bbl. rotary mud, release plug and pumped 100 lbs hulls, and 125 sk cmt. (35-65) 6% total gel. PSI 200

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1-10-72

INV. NO. 4898-41