

KANSAS

*al*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-31-72  
JAN 31 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company  
Complete Address Box 553 Russell, Kansas 67665  
Lease Name Colahan "A" Well No. 12  
Location 330° S of N/4 cor of Sec. 24 Twp. 11 Rge. (E) (W) 17  
County Ellis Total Depth 3403'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling  
Address Box 405 Chase, Kansas 67524 License No. 436  
Operation Completed: Hour 1:45 P Day 26 Month 1 Year 1972

The above well was plugged as follows:

Total Depth 3403' 8 5/8 csg set at 1042' cwc 285 sk.

5 1/2 csg set at 3397' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3385-3403) dumped 5 sk cmt W/dump bailer. (3350-3385)

Cutoff and recovered 2300' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released plug and  
pumped 85 sk cmt.

I hereby certify that the above well was plugged as herein stated.

RECEIVED

Signed: Lee J. Murray  
Well Plugging Supervisor

DATE 2-1-72  
INV. NO. 5084-W