

15-051-03427-0000

Form CP-3
Rev. 6-4-68

KANSAS

AL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company
Complete Address Box 553 Russell, Kansas 67665
Lease Name Colahan "A" Well No. 16
Location NW NE SW Sec. 24 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3444'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas License No. 436
Operation Completed: Hour 3:10 P Day 26 Month 1 Year 1972

The above well was plugged as follows:

Total Depth 3444' 8 5/8 csg set at 1120' cwc 300 sk.
5 1/2' csg set at 3440' cw 100 sk cmt.
Filled 5 1/2' csg W/sd (3425-3444) Dumped 5 sk cmt W/dump bailer. (3385-3425)
Cutoff and recovered 1700' of 5 1/2' csg.
Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released plug and
pumped 95 sk cmt.

I hereby certify that the above well was plugged as herein stated.

RECORDED
DATE 2-1-72
INV. NO. 5088-W

Signed: *Lee F. Manning*
Well Plugging Supervisor