

KANSAS

AL STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Calahan "A" Well No. 11

Location NE SE NW Sec. 24 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3419'
3630'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 504 Chase, Kansas License No. 436

Operation Completed: Hour 5:30 P Day 23 Month 8 Year 1971

The above well was plugged as follows:

Total Depth 3419' 8 5/8 csg set at 1040' cwc 300 sk comm.

5 1/2 csg set at 3413' cw 100 sk comm.

4" liner set & cemented (3301-3630) with perf. (3436-3450) after setting BP at 3453'.

5 1/2 csg squeezed and circulated to surface thru Dakato Section. No pipe recov.

Ran 2" tubing to 3258' -circulated to surface with 30 sk gel & water W/200 lbs

hulls -Displaced 30 sk 60-40 poz W/2% gel (2975-3258)

Pulled tubing to 490' & circulated 70 sk 60-40 poz W/2% gel to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *L. E. Massey*
Well Plugging Supervisor

DATE 8-31-71

INV. NO. 4239-W