

15-051-03417-0000 9 SP

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company
Complete Address Box 553 Russell, Kansas 67665
Lease Name Colahan "A" Well No. 6
Location C N/2 N/2 NW Sec. 24 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3383'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas License No. 436
Operation Completed: Hour 12:30 P Day 11 Month 6 Year 1971

The above well was plugged as follows:

Total Depth 3383' 8 5/8 csg set at 1002' cwc 450 sk.
5 1/2 csg set at 3374' cw 100 sk cmt.
Filled 5 1/2 csg W/sd (3315 -3383) Dumped 5 sk cmt W/dump bailer. (3280-3315)
Recovered 1000' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel W/3 sk hulls, release plug and pumped 130 sk
50-50 poz 6%. Max. pres. 1000 lbs. SI pres. 750 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6-14-71
INV. NO. 3851-W

Signed: Geo J. Manning
Well Plugging Supervisor