

15-051-03414-0000

Form CP-3
Rev. 6-4-68

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address P. O. Box 553 Russell, Kansas 67665

Lease Name Colahan "A" Well No. 3

Location C SW SW NW Sec. 24 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3451'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 10 A Day 10 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 3451' 8 5/8 csg set at 1045' cwc 300 sk.

5 1/2 csg set at 3437' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3420-3451) Dumped 5 sk cmt W/dump bailer. (3385-3320)

Cutoff and recovered 42 jts (1200') of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug

and pumped 100 sk "Halib. -light" cmt. Max. pres. 300 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Murray
Well Plugging Supervisor

DATE 8/11/72
INV. NO. 6150-W