

15-051-03412-0000

Form CP-3
Rev. 6-4-68

KANSAS

v
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Colahan "A" Well No. 1

Location NW NW NW Sec. 24 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3407'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 10 A Day 29 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 3407' 8 5/8 csg set at 1020' cwc 325 sk.

5 1/2 csg set at 3400' cw 100 sk cmt.

Filled 5 1/2 csg W/ad (3380-3407) Dumped 5 sk cmt W/dump bailer. (3355-3380)

Cutoff and recovered 1740' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gas & water W/300 lbs hulls, released 8 5/8 plug

and pumped 85 sk HALCO-LIGHT by HOWCO. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
MAR 3-3-72
INV. NO. 5266-12

Signed: [Signature]
Well Plugging Supervisor