

15-051-03428-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1972  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Colahan "A" Well No. 17

Location NW SW NE Sec. 24 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3413'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No.       

Operation Completed: Hour 11:45 A Day 24 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 3413' 8 5/8 csg set at 1055' cwc 300 sk.

5 1/2 csg set at 3406' cw 100 sk cmt.

Set 5 1/2 wood plug at 3200' -poured 10' sand -dumped 5 sk cmt W/dump bailer. (3155-3200)

Cutoff and recovered 1747' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released plug and  
pumped 90 sk Halib. Light Cmt. Pres. 450 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo J. Murray*  
Well Plugging Supervisor

2/28/72  
5230-U

WV. NO.