

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Gove County, Sec. 27 Twp. 12 Rge. (E) 31 (W)

NORTH


Locate well correctly on above  
Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE  
Lease Owner The Globe Oil & Refining Co.  
Lease Name Wolfe Well No. 1  
Office Address 301 So. Market, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-19-51 19  
Application for plugging filed Verbal 11-19-51 19  
Application for plugging approved " 11-19-51 19  
Plugging commenced 11-19-51 19  
Plugging completed 11-19-51 19  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4812 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi		4662		8 5/8"	254	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed first plug to 240' and cemented with 15 sx. Pushed second plug to 35' and cemented with 10 sx.

11-24-1951

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Leo L. Ross (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Leo L. Ross*

301 So. Market, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1951

*Frances Leslie*  
Notary Public.

My commission expires July 21, 1954

PLUGGING  
FILE SEC 27 T 12 R 31 W  
BOOK PAGE 125 LINE 42

15-063-00060-00-00

DRILLERS LOG

COMPANY: The Globe Oil & Refining Co  
CONTRACTOR: Pabco Drilling, Inc.

LOCATION: NE NE NE  
27-12S-31W  
Gove County  
Kansas

FARM NAME: No. 1 Wolfe

COMMENCED: 10-27-51  
COMPLETED: 11-19-51

PRODUCTION: D & A

CASING USED:  
3-5/8" 262' cas w/150 sz

Shale & Shells	250	
Shale	262	
Shale & Shells	660	
Shale	1160	ST @ 1000 off 10 d plugged back to 435
Anhydrite	1560	ST @ 1000, 1200, & SLM OK
Shale & Shells	1650	ST @ 1700 OK
Shale, Shells & Red Beds	2370	
Lime	2410	
Red Beds & Shale	2520	ST @ 2500 & SLM OK
Shale & Shells	2720	
Lime & Shale	2805	ST & SLM OK @ 3000
Lime	3973	ST & SLM OK @ 3500
Lime & Shale	4209	ST & SLM OK @ 4175
Lime	4237	
Shale & Lime	4278	
Sand	4298	
Lime & Shale	4316	
Lime	4345	
Lime & Shale	4398	
Lime	4471	
Lime & Shale	4537	
Lime	4568	
Shale & Sand	4605	
Shale & Lime	4625	
Sandy Shale & Lime	4551	
Sandy & Lime	4653	
Lime	4670	
Lime & Shale	4688	
Lime	4760	
Total Depth	4812	

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK)

I, D. J. Briggs, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

11-24-1951  
NOV 24 1951  
DIVISION  
KANSAS

PABCO DRILLING, INC.

By D. J. Briggs  
D. J. Briggs, President

Subscribed and sworn to before me this 21st day of November, 1951

Notary Public

My commission expires March 2, 1953

PLUGGING  
FILE SEC 27 T 12 R 31W  
BOOK PAGE 125 LINE 42