

15-051-22744-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 24 TWP. 11S RGE. 17 E/W
Location as in quarters or footage from lines:
1450' FSL - 300' FWL

Locate Well
correctly on above
Section Platt.

Lease Owner Cities Service Company
Lease Name Colahan "A" Well No. 36
Office Address 209 E. William, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed December 18, 1981
Application for plugging filed December 18, 1981-Verbal
Plugging commenced December 18, 1981 Approval
Plugging completed December 18, 1981
Reason for abandonment of well or producing formation
Uneconomical for production

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation _____ Depth to top _____ bottom T.D. 3668'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	814'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug with 50-50 Pozmix "A" plus 4% gel plus 3% CaCl as follows:
Spot 70 sacks at 780'
Spot 40 sacks at 300'
Bridged with plug and hulls at 40'
10 sacks cement to surface
Plug rat hole with 10 sacks

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pioneer Drilling Co., Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

E. W. Peterman (employee of owner) ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
E. W. Peterman
(Address)

209 E. William, Wichita, KS 67202

10 day of May, 19 82



My Commission expires: 2-27-85

Jacqueline Pierce
Jacqueline Pierce - Notary
RECEIVED
STATE CORPORATION COMMISSION
5-11-82
MAY 11 1982

CONSERVATION DIVISION
Wichita, Kansas