

15-051-05554-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Ellis County, Sec 24 Twp 11S Rge. (E) 17 (W)
Location as "NE/CNWxSWx" or footage from lines NE SW SE
Lease Owner Cities Service Oil Company
Lease Name Colahan "C" Well No. 4
Office Address Box 553 Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-15 19 41
Application for plugging filed 1-24 19 72
Application for plugging approved 1-25 19 72
Plugging commenced 2-8 19 72
Plugging completed 2-29 19 72
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production June 19 67
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey
Producing formation Arbuckle Depth to top 3406' Bottom 7' Pen. Total Depth of Well 3413 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1045'	None
				5 1/2"	3407'	1069'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed 5 1/2" plug to 3250', dumped sand 3250' to 3240' and 5 sx. cement 3240' to 3205'. Pulled on 5 1/2" casing. Parted at 96,000 lbs. Pulled 35 Joints (1068.80'). Halliburton pumped in 2 1/2 sx. hulls, 20 sx. gel. 1250' to 450', 8 5/8" plug, 1/2 sx. hulls, 90 sx. cement 450' to surface.


RECEIVED
STATE CORPORATION COMMISSION
APR 7 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
E. W. Peterman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 553 Russell, Kansas 67665 (Address)

Sworn to before me this 5th day of April, 1972



[Signature] Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well No. 4 Farm Colahan "C"
 Location 990' N. & 990' E. of S/4 Cor. Sec. 24 T. 11 R. 17-7
 Elevation 1933 County Ellis State Kansas
 Drig. Comm. June 27, 1941 Contractor Kabee Oil & Gas Company
 Drig. Comp. July 15, 1941 Acid 1000 gals. (7-20-41)
 T. D. 3413' Initial Prod. Echometer Potential: 8154 oil, no water, 24 hrs.

CASING RECORD:
 8-5/8" @ 1045' com. 300 ex Victor,
 8 ex Aquagel & 3 ex C. G.
 5-1/2" @ 3407' com. 100 ex cement

FORMATION RECORD:

shale	0-40
shale & shells	530
sand & shale	630
shale, shells & sand	840
shale & shells	1045
shale	1127
anhydrite	1170
shale & shells & red bed	1330
shale & shells	1530
salt & shale	1733
shale & shells	1785
lime broken	2316
lime & shale	2574
shale & shells	2808
shale & lime	2871
lime broken	2890
lime	3106
broken lime	3140
lime	3188
shale & lime	3226
lime	3346
lime broken	3412
3412 bot. TD = 3408 SLM	
dolomite	3413 T. D.

Corr. Top Arbuckle 3406 (-173)
 Penetration 7'
 Total Depth 3413

Fillup: 1325' oil in 45 mins.
 1900' oil in 1-1/4 hrs.
 2500' oil in 1-3/4 hrs.

Syfo: 500' 0°
 1000' 0°
 1500' 0°
 2000' 0°
 2500' 0°
 3000' 0°

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 25 1972
 CONSERVATION DIVISION
 Wichita, Kansas