

15-051-03475-0001

WELL PLUGGING RECORD  
K.A.R.-82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- NA  
LEASE NAME Colahan A  
WELL NUMBER 26

TYPE OR PRINT  
NOTICE: Fill out completely and return to Cons. Div. office within 30 days.  
4290' ft. from S Section Line  
2310 RTACC  
330' ft. from E Section Line

LEASE OPERATOR OXY USA INC.  
ADDRESS P.O. Box D, Plainville, KS  
PHONE # 785-434-7681 OPERATOR'S LICENSE NO. 5447  
Character of Well SWD  
(Oil, Gas, D&A, SWD, Input, Water Supply)

Spot Location \_\_\_\_\_  
SEC 24 TWP 11 S RGE 17 or (W)  
COUNTY Ellis  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 12-1-97  
Plugging Completed 12-1-97

The plugging proposal was approved on 11-4-97 (date)  
by David P. Williams - Hays, KS (KCC District Agent's Name)

Is ACO-1 filed? On File If not, is well log attached? \_\_\_\_\_

Producing Formation OH Arbuckle Depth to Top 3495' Bottom 3843' T.D. 3843'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
		5'	1079'	8-5/8"	1079'	0'
		0'	3495'	5-1/2"	3495'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

\*\*\* See back for details \*\*\*

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. NA  
Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF Kansas COUNTY OF Rooks, ss.  
J.D. Hininger (Employee of Operator) or (Operator) of above-described well, being first duly sworn

on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.D. Hininger  
(Address) P.O. Box D, Plainville, KS

RECEIVED

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1997

DEC 31 1997  
12-31-97

Sheryln Axelson Notary Public

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:  
5-20-2000



15-051-03475-0001

OXY U.S.A., Inc.  
Well Chronological Report

12/30/97

COLAHAN A 26

=====

12/26/97 JOB: Plug and Abandon; CMIC: GEORGE YOUNGER  
 12/1/97 - Plug and Abandon - Rigged up and ran 2 1/2" tbg. to 3400' -  
 Mixed and pumped 200 sks. 60/40 pozmix plus 10% gel plus 500 lbs. hulls  
 - Pulled tbg. to 1800 ft. and pumped 80 sks. same cement and circulated  
 to surface - Pulled rest of tbg. and topped off 5 1/2" csg. w/ 10 more  
 sacks. Pumped dn 8 5/8 w/ 15 sks. and 50lbs. hulls shut in with 300  
 psi. - State witness Dennis Hamel - Plugged at 10:30 AM 12/1/97  
 12/22/97 - Topped off 5 1/2" with 5 sks.  
 12/26/97 - Cut off csg. - cleaned up location. - complete  
 L/E \$ 875; MAT \$ 5193; CUM: L/E \$ 875, MAT \$ 5193;

RECEIVED  
STATE CORPORATION COMMISSION

DEC 31 1997

CONSERVATION DIVISION  
Wichita, Kansas