

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-05876-0000

API NUMBER 15 N/A

LEASE NAME Colahan C

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

2310 Ft. from S Section Line

1650 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 24 TWP. 11S RGE. 17 (x) or (W)

ADDRESS P. O. Box 26100

COUNTY Ellis

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 3/21/41

Character of Well Oil

Plugging Commenced 8/17/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/18/94

The plugging proposal was approved on _____ (date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Bemis-Shutts Depth to Top 3395 Bottom 3402 T.D. 3402

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put in	Pulled Out
<u>Bemis-Shutts</u>	<u>Oil</u>	<u>3395</u>	<u>3402</u>	<u>8 5/8</u>	<u>1075</u>	
				<u>5 1/2</u>	<u>3396</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

RIH w/2 1/2 tbq w/notched collar on btm of tbq. Hit bridge @ 2675. MIRU mud pump & power swivel. Drill thr. bridge & circ'd out mud. Hit second bridge @ 2885 drilled thr. & circ'd clean. Run tbq to PBTD of 3402'. Circ'd clean. POOH w/ tbq. Pump down 5 1/2 csq 300sx of 40/60 pozmix A w/ 10% gel & 300# cotton seed hulls. Max press 600 psi. SI 200 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service License No. 6426

Address P. O. Box 426, Victoria, KS 67671-0426

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 21th day of August

[Signature]
Notary Public
8-21-96
STATE OF OKLAHOMA
CORPORATION COMMISSION
RECEIVED
AUG 24 1994
WICHITA, KANSAS
Form CP-4
Revised 05-88

My Commission Expires: 8-31-94

WELL RECORD

Company Cities Service Oil Co. Well No. 2 Farm Colahan "C"
 Location 330' south & 990' east of Center Sec. 24 T. 11 R. 17-W
 Elevation 1923 County Ellis State Kansas
 Drig. Comm. February 11, 1941 Contractor Habee Oil & Gas Company
 Drig. Comp. March 21, 1941 Acid 500 gallons March 21, 1941.
 T. D. 3402 Initial Prod. Echometer potential: 13,343 oil, no water, 24 hours.

CASING RECORD:

8-5/8" 1075' cem. 300 Ash Grove & 8 Aquagal
 5-1/2" 3396' cem. 100 Victor

FORMATION RECORD:

shale	0-585
sand	635
shale & shells	820
sand	865
red bed & shale	957
shale	1075
red bed	1090
lime	1135
shale & shells	1530
salt & shale	1720
shale & lime	1953
lime & shale	2413
lime broken	2549
lime & shale	2640
shale	2794
lime	3051
lime & shale	3171
lime broken	3303
lime	3333
lime & shale (top Arbuckle	
3396)	3397
3397 Rot. T.D. = 3396 S.L.M.	
dolomite	3402 T.D.

Corr. Top Arbuckle	3395 (-147)
Penetration	7'
Total Depth	3402

Fillup: 1500' oil in 30 mins.
 2700' oil in 1 hr. 40 mins.
 2850' oil in 6 hrs. 40 mins.

Byfo: 1000'	0°
1500'	0°
2000'	0°
2500'	0°
3000'	0°

3395
 1923
 -1472

RECEIVED
 KANSAS CORPORATION COMMISSION

JUL 20 1994

CONSERVATION DIVISION
 WICHITA, KS