

15-051-03432-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Well was completed on

API NUMBER 2-13-41

LEASE NAME Colahan A

WELL NUMBER 21

2970 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 24 TWP. 11S RGE. 7 X (W) or (W)

COUNTY Ellis

Date Well Completed 2-13-41

Plugging Commenced 11-19-87

Plugging Completed 11-23-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #4

Well was completed on

Is ACO-1 filed? 2-13-41 If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top _____ Bottom 3400' T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	OH	3400	8-5/8"	1084'	
				5-1/2"	3393'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran 2-3/8" tubing to TD 3400'. Pumped 25 sx. 60/40 Poz w/6% gel. Cement plug from 3349-3123'. Pulled tubing to 3123'. Pumped 13 sx gel spacer from 3123-1788'. Pulled tubing to 1788'. Pumped 200 sx. & 500# hulls. Cement plug from 1788 to surface.

State Witness: Mr. Dennis Hamel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. _____

Address Box 678, N. Highway 281, Great Bend, KS 67530

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

STATE CORPORATION COMMISSION
1-28-88

Del G. Oliver, Engineering Manager

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well was filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver

3545 NW 58th Street

(Address) Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 88

Jessie Jo Howell

Notary Public

My Commission Expires: 4-24-89