

15-051-03412-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202
NORTH

WELL PLUGGING RECORD

Ellis County, Sec. 24 Twp 11S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines ~~SW~~ NE NW NW NW
Lease Owner Cities Service Oil Company
Lease Name Colahan 'A' Well No. 1
Office Address Box 553 Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-1 19 39
Application for plugging filed 11-12 19 71
Application for plugging approved 11-15 19 71
Plugging commenced 2-5 19 72
Plugging completed 2-29 19 72
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 8-17 19 68
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey
Producing formation Arbuckle Depth to top 3399' Bottom 8' Pen. Total Depth of Well 3407 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1020'	None
				5 1/2"	3400'	1732'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Checked bottom, ran sand to 3380', dumped 5 sx. cement
3380-3335. Shot 5 1/2" casing at 1834' and 1740' Pulled 53
Jts. (1731.94') Halliburton pumped in 2 1/2 Sx. Hulls, 20 Sx.
Gell 1225' to 425', 8 5/8" plug, 1/2 sx. hulls 85 sx. cement
425' to surface.

RECEIVED
STATE CORPORATION COMMISSION
APR 6 - 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
E. W. Peterman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. W. Peterman*
Box 553 Russell, Kansas 67665
(Address)



SUBSCRIBED AND SWORN to before me this 4th day of April, 19 72

James F. Kyger
Notary Public.

15-051-03412-0000

Company Cities Service Oil Co. No. 1 Farm Colahan "A"

Location 330' S., 330' E., NW Corner Sec. 24 T. 11 R. 17-W

Elevation 1097 County Ellis State Kansas

Drilling Commenced July 18, 1939 26,000 gal. of water

Date Completed Aug. 1, 1939 Initial Production (Robo-Meter, Max. 3300)

Contractor J. E. Huber Company Acidized 300 gallons

Total Depth 3407'

CASING RECORD:

8-5/8" 1020' con. 325 con., 8 Aquagel
 5-1/2" 3400' con. 100 con., 15 Aquagel

PILLUP: 300' in 30 min.
 500' in 1 hour
 2050' in 2 hours
 2950' in 3 hours

FORMATION RECORD:

shale & shells	0-345
sand & shale	400
shale & shells	590
sand iron shells & shale	918
shale & shells	1020
shale & red bed	1110
lime	1140
red bed	1250
shale	1450
silt	1500
shale	1630
shale & shells	1730
broken lime	1810
lime broken	1910
shale	1955
lime broken	2079
broken lime	2125
shale & shells	2190
shale	2250
shale & shells	2297
shale & lime	2359
shale	2590
lime	2529
shale & shells	2675
lime	2715
shale & lime	2841
lime broken	2923
lime	3088
lime broken	3150
lime	3240
lime broken shale	3323
lime	3396
core 3396-3402, 5' recovery	
shale	3396-3401
Arbuckle lime	3401-3402
T. D. rotary dolomite	3402-3400 G.L.M.
	3407
top Arbuckle	3399 corrected
total depth	3407
penetration	0'

SYFO: 300' OK
 550' OK
 1500' OK
 2000' OK
 2500' OK
 3000' OK

Rotary 3399
 Cable Tools 3407

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 15 1971
 CONSERVATION DIVISION
 Wichita, Kansas