

4-071112

8-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,477-00-00

NW NW SE /4 SEC. 29, 12 S, 30 W
2090 feet from S section line
2020 feet from E section line

Operator license# 30606

Lease Abell well # 1-29

Operator: Murfin Drilling Co., Inc.

County Gove

Address: 250 N. Water - Suite #300
Wichita, Kansas 67202
Scott Robinson

Well total depth 3930 feet 127.73
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 230 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 14 Month: August Year: 94

Plugging proposal received from: Keith Vanpelt

Company: Murfin Drilling Company Phone: 316-267-3241

Were: 8 5/8" - 230' S.P. cwc. w/160 sxs. 50/50 pozmix - 2% gel - 3% c.c.
By: Allied. Elv. 2792' - Anhy. 2245' - No circulation problems - Miss. Well.
Mud condition 48 vis. - 9.7 Wt. - 9 Water loss. Proposal 190 sxs. 60/40
pozmix - 6% gel - and 1 sx. flocele. Circulate hole. 42 - 45 vis. mud.
Spot and displace all cement with drill stem with heavy mud between all
plugs. 25 sxs. @ 2225' - 100 sxs. with 1 sx. flocele @ 1090' - 40 sxs. @
280' - 10 sxs. @ 40' and 15 sxs. in rathole - circulate.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 6:00P.M., Day: 14, Month: August, Year: 94

Actual plugging report: Murfin ordered 190 sxs. 60/40 pozmix - 6% gel -
1 sx. flocele. Circulated hole - 42 to 45 vis. Spotted and displace all
cement through drill pipe with heavy mud between all plugs.

1st. plug @ 2255' w/25 sxs. cement.

2nd. plug @ 1090' w/100 sxs. cement and 1 sx. flocele.

3rd. plug @ 280' w/40 sxs. cement.

4th. plug @ 40' w/10 sxs. cement.

15 sxs. in rathole (circulated)

Remarks: By: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO STATE CORPORATION COMMISS

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X NO

Plugged through TUBING , CASING X. Elevation: 2792 GL

I did[] did not[X] observe the plugging.

INVOICED

DATE 9-5-94

WV. NO 41090

RECEIVED
STATE CORPORATION COMMISS
08-23-1994
AUG 23 1994
CONSERVATION DIVISION
WICHITA, KANSAS
Agent) *Marion J. Schmidt*