

6- 090447

11-24

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,359-00-00

NW NW NW /4 SEC. 01, 12 S, 31 W
4950 feet from S section line
4950 feet from E section line

Operator license# 30269

Lease R.J. Stephens A well # 1

Operator: Argent Energy, Inc.

County Gove

Address: 110 South Main, Suite 510
Wichita, Kansas 67202-3745

Well total depth 4670 feet ^{151.77}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 265 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie Drilling Company, Inc. License# 5422

Address: Wichita, Kansas

Company to plug at: Hour: Day: 21 Month: November Year: 1990

Plugging proposal received from: Tony Martin

Company: Abercrombie Drlg. Co, Inc. phone: (316)262-1841

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2460 feet with 20 sacks Rat hole: 15 sacks

2nd plug @ 1585 feet " 100 " Mousehole: sacks

3rd plug @ 315 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

5th plug @ feet "

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III

Plugging operations attended by agent? All[], Part[] None [X]
Wichita, Kansas

Completed: Hour: 5:00 PM, Day: 24, Month: November, Year: 1990

Actual plugging report: Hole reported plugged as above.

Order 185sx 60/40 pozmix w/ 6% gel and 1sx celloflake or flowcel.

Remarks: Elevation: 2934 GL, Anhydrite depth: 2458 - feet

Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did[] / did not[X] observe the plugging. Ed Schumacher

INVOICED

DATE 12-10-90

HTV. NO. 30199

Ed S.

Ed Schumacher P.I.R.T. III
(agent)

RECEIVED
STATE CORPORATION COMMISSION
12-06-1990
DEC 6 1990