

4 060032

11-21

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,292 -00-00  
150' S of NW SW, SEC. 22, T 12 S, R 30 W/EK  
1830 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Lease Name Beougher Well # #1-Twin

Operator: Anderson Energy, Inc.

County Gove 145.60

Name &

Address 200 E. First St. Suite 414

Well Total Depth 4480 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drig Co. License Number 5420

Address Wichita, KS

Company to plug at: Hour: 11:20PM Day: 21 Month: November Year: 19 89

Plugging proposal received from Don Danel

(company name) White & Ellis Drig. (phone) 316-263-1102

were: Space all plugs through drill pipe with heavy drilling mud.  
Order 185 sxs, 60/40 pos 6% gel and 1/4# floccul per sx.

Arbuckle not reached.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXXXX

Operations Completed: Hour: 11:20PM Day: 21 Month: November Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2300' with 20 sxs. Anhydrite 2278-2306'  
2nd plug at 1420' with 100 sxs. Dakota 1119-1419'  
3rd plug at 370' with 40 sxs. Surface pipe to 320'  
4th plug at 40' with 10 sxs. with wiper plug at 40' rathole with 15 sxs.

Remarks: Allied Cementing  
(If additional description is necessary, use BACK of this form.)

REC-1 1000  
12-01-1989  
CO. GENERAL INVESTIGATIVE DIVISION  
WICHITA, KANSAS

INVOICED  
(If you did not observe this plugging.)

DATE 12-7-89

INV. NO. 26664

*Herb S.*

Signed Herb Deines  
(TECHNICIAN)

Herb Deines