

4-060924

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

7-15

API Number: 15-109-20,572-0001

N2 N2 NE /4 SEC. 02, 12 S, 32 W
4950 feet from S section line
1320 feet from E section line

Operator license# 31251

Lease: Richard Mathers OWWO Well # 1

Operator: Wabash Energy Corporation

County: Logan

Address: P.O. Box 595
Lawrenceville, IL 62439

Well total depth 4840 157.30 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 253 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: 150 N. Main - Suite #801 - Wichita, Kansas 67202

Company to plug at: Hour: 12:30 A.M. Day: 15 Month: July Year: 1996

Plugging proposal received from: Tony Martin

Company: Abercrombie RTD, Inc. Phone: 316-262-1841

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.
OWWO - Cleaned out, tested and replugged. Non-commercial.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 18 1996
0748-1996
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 2:30 A.M. Day: 15 Month: July Year: 1996


Actual plugging report:

- 1st. Plug at 2560' w/25 sxs. - Anhydrite 2553' - 2577'.
- 2nd. Plug at 1560' w/100 sxs. - Surface pipe to 257'.
- 3rd. Plug at 300' w/40 sxs. -
- 4th. Plug at 40' w/10 sxs.
- 15 sxs in rathole.
- 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 3008 GL

I did [] did not [X] observe the plugging.


(agent)
Form CP-2/3

DATE JUL 25 1996

INV. NO. 46105

7-15