

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-063-21,454-00-00

SE SE SE /4 SEC. 31, 12 S, 31 W  
330 feet from S section line  
330 feet from E section line

Operator license# 31016

Lease Leo well #64-16-31

Operator: Diversified Operating Corp.

County Gove

Address: 1675 Larimer St.  
Suite 850  
Denver, CO 80202

Well total depth 4750 feet *154.37*  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: P.O. Box 506 - Russell, Kansas 67665

Company to plug at: Hour: A.M Day: 02 Month: May Year: 93

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone:                     

Were: Order 190 sxs. 60/40 poz. - 6% gel. with 1/4# flocele.  
Spot plugs through drill pipe with heavy mud between all plugs.  
1st. plug @ 2485' w/25 sx.  
2nd. plug @ 1615' w/100 sx.  
3rd. plug @ 270' w/40 sx.  
4th. plug @ 40' w/10 sx. and wiper plug.  
Rathole with 15 sx. - Anhy - Perf. @ 2474'. Dakota @ 1317'.

Plugging Proposal Received by: Ken Kuhn  
Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 3:45P.M., Day: 02, Month: May, Year: 93

Actual plugging report: Hole reported plugged as above.  
Order 190 sx. 60/40 pozmix with 6% gel. - 1/4# flocele.

**RECEIVED**  
KANSAS CORPORATION COMMISSION

*05-12-1993*  
MAY 12 1993

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Cement Co: Allied Cement Company  
Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO X Dakota plug: YES     , NO       
Plugged through TUBING X, CASING     . Elevation: 2967 GL

I did      / did not X observe the plugging.

*Ken Kuhn*  
*OK* (agent)

**INVOICED**

DATE 5-18-93

INV. NO. 37733