

11-12

4-071075

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-063-21,467-00-00

NE NW SE /4 SEC. 13, 12 S, 31 W  
2310 feet from S section line  
1650 feet from E section line

Operator license# 5316 Lease Weber well # 1

Operator: Falcon Exploration, Inc. County Gove

Address: 155 N. Market #1000 Well total depth 4572 feet <sup>148.59</sup>  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Jim Thather Surface pipe 8 5/8 Inch @ 319 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Blue Goose Drilling - Halliburton License# -

Address: Great Bend, Kansas 67530 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 12 Month: November Year: 93

Plugging proposal received from: Martin Miller

Company: Blue Goose Drilling Phone: 316-793-6031

Were: 8 5/8" - 319' S.P. cwc. w/210 sxs. class A - 3% c.c. - 1/4# flocele. By Halliburton. Elv. 2907' - Miss. Well - Anhy. 2395' - No circulation problems - mud condition 46 vis. - 9.5 wt. - 10 water loss. Proposal 190 sxs. 60/40 pozmix - 6% gel - 1 sx. flocele. Circulate hole, spot and displace all cement through drill pipe. 25 sxs. @ 2400' - 100 sxs. w/1 sx. F.C. @ 1557' - 40 sxs. @ 360' - 10 sxs. @ 40'. 15 sxs. rathole - circulate with pipe.

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 2:45A.M., Day: 12, Month: November, Year: 93

Actual plugging report: Blue Goose ordered 190 sxs. 60/40 posmix - 6% gel and 1 sx. flocele. Circulated hole - spotted and displaced all cement through drill pipe. Heavy mud between all plugs.

- 1st. plug @ 2400' w/25 sxs. cement.
- 2nd. plug @ 1557' w/100 sxs. cement with 1 sx. flocele.
- 3rd. plug @ 360' w/40 sxs. cement.
- 4th. plug @ 40' w/10 sxs. cement.
- 15 sxs. cement in rathole (circulated)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 24 1993  
11-24-1993  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: By: Halliburton Service.  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING  , CASING  . Elevation: 2907 GL

I did  [ ] observe the plugging. Marion J. Schmidt  
(agent)

**INVOICED**  
DATE 12-3-93  
INV. NO. 39326