

6070158

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-03424-0000  
N<sup>1</sup>/<sub>4</sub>, SEC. 24, T. 11 S, R. 17 W E  
660 feet from N S section line  
1650 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name COLAHAN Well # A-13

Operator: CITIES SERVICES INC.  
Name & Address MID-CONTINENT NORTH REGION

County ELLIS CO

209 E. WILLIAM #800  
SUTTON PLAZA, WICHITA, Mo.  
67208

Well Total Depth 3387 110.08 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 1068

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HALLIBURTON CONT. COMPANY License Number \_\_\_\_\_

Address EAST HWY 40 HAYS, KANSAS 67601

Company to plug at: Hour: 9:00 AM Day: 5<sup>TH</sup> Month: JUNE Year: 19 84

Plugging proposal received from DAN HOFFMAN & DON SHELDEN.

(company name) CITIES SERVICES INC. (phone) 913-434-2350

were: 8 5/8" 1068' CUC #285 SK CNT, 5 1/2" SET @ 3380' EL #1100 SK CNT  
SQUEEZED @ 93' EL #1/A. ALSO @ 2434' EL #1/A. Plug Back 3387' EL

7' EL OPEN HOLE - NO PIPE RECOVERY ELV. 1884' EL ANH 1054'

ORDER 400 SK 50/50 POZMIX GEL - CA-CL, 5<sup>SK</sup> HULLS, 6<sup>SK</sup> GEL, 2<sup>SK</sup> FLAME,

AND 5 1/2" PLUG, PUMP IN WITH PUMP TRUCK.

RECEIVED \_\_\_\_\_ Plugging Proposal Received by [Signature]  
(TECHNICIAN) DOIC

STATE CORPORATION COMMISSION  
Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
JUN 11 1984

Operations Completed: Hour: 2:05 PM Day: 5<sup>TH</sup> Month: JUNE Year: 19 84

ACTUAL OPERATIONS REPORT ORDERED 400 SK 50/50 POZMIX GEL - CA-CL, 6<sup>SK</sup> GEL,  
5<sup>SK</sup> HULLS, 2<sup>SK</sup> FLAME, AND 5 1/2" PLUG.

ANNULUS FULL OF CEMENT TO TOP. - PUMPED IN 5 1/2" CS9

200<sup>SK</sup> CNT. #3<sup>SK</sup> HULLS MIXED IN #1 TO<sup>SK</sup>, 6<sup>SK</sup> GEL #1/2<sup>SK</sup> HULLS,

50<sup>SK</sup> CNT #1/2<sup>SK</sup> FLAME AND 100<sup>SK</sup> CNT. WAITED 3 HRS AND

PUMPED IN 35<sup>SK</sup> CNT., MAX PSI 200 PSI, CEMENTED BY

Remarks: HALLIBURTON CONT.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(did / ~~not~~) observe this plugging.

DATE 6-12-84

Signed [Signature]  
(TECHNICIAN) DOIC 3

INV. NO. 1966