

11-19-87 15-051-03432-0000

6 040818

2-13-41

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_  
\_\_\_\_\_, SEC. 24, T. 11 S, R. 17 (W/E)  
2970 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Colahan A Well # 21

Operator: Cities Service Oil and Gas  
Name & Address: 3545 N. W. 58th  
Oklahoma City, Ok 73112

County Ellis 110.50

Well Total Depth 3400 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1084' w/325 cw

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cementing License Number \_\_\_\_\_

Address Hays, Kansas

Company to plug at: Hour: 12:30PM Day: 19 Month: November Year: 19 87

Plugging proposal received from Don Sheldon

(company name) Cities Service (phone) \_\_\_\_\_

were: 5 1/2" at 3393' w/100 sks cement. Sq at 2120' w/75 sks cement. Sq at 1940' w/75 sks. Sq at 150' w/75 sks cement. P.B. w/sand to 3349' (W.L.M.)

Bad casing at 780' - 1370'.

Ordered 250 sks 60/40 Poz 6% Gel w/1/2# Flocele

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:15PM Day: 19 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT Ran tubing to 3338'. Spotted 20 sks cement.

Pulled tubing to 3128'. Spotted 13 sks gel. Pelled tubing to 1850'.

Spotted 220 sks cement w/5 sks Hulls. Pulled tubing sq add .20 sks cement, in casing. Max Psi. 400# S.I. 400#. Pressured up annulus 1400#.

12-16-87

DEC 16 1987

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel

DATE 1-6-88

INV. NO. 19359 JAN 14 1988