

15-051-03475-0001

4-041943

D-14,650

12-1

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 8-8-46

NE /4 SEC. 24, 11 S, 17 W
4290 feet from S section line
~~330~~ 2310 feet from E section line

RTKCC

Operator license# 5447
Operator: OXY USA, Inc.
Address: P.O. Box D
Plainville, Kansas 67663

Lease: Colahan "A" Well # 26
County: Ellis 124.90

Well total depth 3843 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 1079 Feet
W/500 sxs cmt.

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Co Tools License# 5447

Address:

Company to plug at: Hour: 8:00 A.M. Day: 1 Month: December Year 1997

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 785-434-7681

Were: 5 1/2" casing set at 3495' w/150 sxs cement. O.H. at 3495' - 3883'.
Ordered 500 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 1000# hulls.
Anhy. At 1080' - Dakota at 575' - W.L.M. 3461'. Ran tubing. Squeezed at 3387' - 3442'.
12-17-97

12-17-97

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 11:05 A.M., Day: 1, Month: December, Year: 1997

Actual plugging report: R.I.H. with tubing to 3400'. Spotted 200 sxs with 500# hulls.
Pulled to 1800' - spotted 75 sxs with 200# hulls. Pulled tubing and squeezed casing with 10
sxs cement. Max. P.S.I. 300#. (Note: cement circulated annulus prior to squeeze.)
R.U. Cementers to 8 5/8" - squeezed casing with 15 sxs cement. Max. P.S.I. 300#.
Job complete.

Remarks:

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: G.L.

I did [] / did not [X] observe the plugging.

Dennis J. Hamel
(agent)

Form CP-2/3

INVOICED
DATE DEC 18 1997
INV. NO. 49748
12-1