

6050155

API NUMBER 15-109-20,349-00-06

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C N<sup>1</sup>/<sub>2</sub> E<sup>1</sup>/<sub>2</sub> NW, SEC. 4, T. 12 S, R. 33 W/E  
3960 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9746

Lease Name D.M. Moore Well # 1

Operator: Wilkar Oil Company

County Logan 155.61

Name & Address: P.O. BOX 3225

Well Total Depth 4788 feet

Santa Fe Springs, Ca. 90670

Conductor Pipe: Size 0 feet

Surface Casing: Size 8<sup>5</sup>/<sub>8</sub> feet 307 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, Ks.

Company to plug at: Hour: AM Day: 29 Month: November Year: 19 84

Plugging proposal received from Mort Sherfick

(company name) Murfin (phone) \_\_\_\_\_

were: Order 185 lbs. 50/50 pozmix 6% gel 3% cal cl., 1 sk flo-cel, 1 sk hulls and 8<sup>5</sup>/<sub>8</sub>" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 8:30 AM Day: 29 Month: November Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 2660 w/25 sks

2nd plug @ 1620 w/110 sks 1 sk flo-cel

3rd plug @ 340 w/40 sks

4th plug @ 40 w/8<sup>5</sup>/<sub>8</sub>" plug 1 sk hulls and 10 sks cmt

10 sks in Rat Hole

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1984

12-10-1984  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Cemented by Sun

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 12-13-89

Signed Arthur P. Leiker 12-10  
(TECHNICIAN)

INV. NO. 5984 11-29 JAN 14 1985

Holt

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 9 30 84  
month day year

API Number IS- 109-20, 349-00-00

OPERATOR: License # 9746  
Name Wilkar Oil Company  
Address P.O. Box 3225  
City/State/Zip Santa Fe Springs, CA 90670  
Contact Person Charles Ed Harris  
Phone (316) 265-9524

CW/2 E/2 NW/4 Sec 4 Twp 12 S, Rge 33  East  West  
(location)  
3960 Ft North from Southeast Corner of Section  
3630 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License #  
Name Unknown  
City/State

Nearest lease or unit boundary line 1320 feet  
County Logan  
Lease Name D. M. Moore Well# 1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

If OWWO: old well info as follows:

Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 4744  
Projected Formation at TD Mississippian  
Expected Producing Formations LKC, Cher.

RECEIVED  
STATE CORPORATION COMMISSION  
12-10-1984  
DEC 10 1984  
CONS. DIV. OF STATE CORP. COM. MISSOURI, KANSAS

Depth to Bottom of fresh water 200 feet  
Lowest usable water formation Dakota  
Depth to Bottom of usable water 1600-1800 feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set 250 feet  
Conductor pipe if any required feet  
Ground surface elevation feet MSL  
This Authorization Expires 3-5-85  
Approved By 9-5-84

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 9/5/84 Signature of Operator or Agent Charles Ed Harris

Title District Manager

MHC/USOHE 9/5/84

Form C-1 4/84