

4-080198

9-18

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
WICHITA, KANSAS 67202

API number: 109-20,631-00-00

NE NW SW /4 SEC. 7, 12S, 33 W  
2310 feet from S section line  
990 feet from E section line

Operator license# 6113

Lease Bertrand well # 1-7

Operator: Landmark Energy, Inc. Vess

County Logan

Address: 1861 N. Rock Rd., Suite 205  
Wichita, Kansas

Well total depth 4785 feet  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 357 feet

155.51

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: L. D. Drilling License# 6039

Address: Great Bend, Kansas

Company to plug at: Hour: AM Day: 18 Month: September Year: 1996

Plugging proposal received from: Greg Davidson

Company: L. D. Drilling phone:                     

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2655 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1620 feet " 100 " Mousehole:        sacks

3rd plug @ 400 feet " 40 "

4th plug @ 50 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[    ], Part[    ], None[ X ]

Completed: Hour: AM, Day: 18, Month: September, Year: 1996

Actual plugging report: Hole reported plugged as above.  
Order 190 sx 60/40 pozmix w/ 6% gel and 1/4 # celloflake or flowcel per  
sack.

Remarks: Elevation: 3163 GL, Anhydrite depth: 2645 - 2665 feet

Did not penetrate Arbuckle, cemented by Allied

I did[    ] / did not[ X ] observe the plugging.

*Bruce D. Basye*

Bruce D. Basye Geologist  
(agent)

Form CP-2/3

**INVOICED**

DATE DEC 31 1996

INV. NO. 47191

REC'D 12-18-96  
A 1:05  
RUP