

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corp
Name & Address: Box 723
Hays, Ks. 67601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Oakley, Ks.

Company to plug at: Hour: _____ Day: 26 Month: Oct. Year: 19 89

Plugging proposal received from George Jorgensen

(company name) Beren Corp (phone) _____

were: 8 5/8" set at 332' w/225 sks. 4 1/2" set at 4764' w/250'. Perfs

4600' - 68' PBD 4704. Order 250 sks 65/35 poz 10% gel 2% A-2, 500# hulls. B. J. Titan

Cement Co. Shots at 2650' Anhy and 1800' below Dakota for block squeeze. Wallbrock

Hensley Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15PM Day: 26 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 2600' circ cement blend to surface. Squeeze

4 1/2" w/total of 150 sks. to max psi 200#. Close in psi 200#. Squeeze 8 5/8" annulus w/

100 sks to max psi 300#. Close in psi 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
11-17-1989
NOV 17 1989

Remarks: CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED
Call / Bill XXXXXX to reserve this plugging.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

DATE 11-20-89
INV. NO. 26532

10-26 .15-109-20089-00-00
API NUMBER 15-1977

NW NE, SEC. 7, T 12-S, R 33 W/Ex

4620 feet from S section line

1980 feet from E section line

Lease Name Bertrand Well # 1

County Logan 154.83

Well Total Depth 4764 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 332