

To: **6 031295**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corp
Name & Address: Box 723
Hays, Ks. 67601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Oakley, Ks.

Company to plug at: Hour: AM Day: 27 Month: Oct Year: 19 89

Plugging proposal received from George Jorgenson

(company name) Beren (phone) _____

were: 8 5/8" set at 296' w/250 sks. 4 1/2" set at 4749' w/250 sks. Perf 4326' - 36'.

4669' - 79'. Order plug and common cement. Pull pipe. Order 225 sks 65/35 poz 10% gel

500# hulls. B. J. Titan Cement Co. Hensley, Wellbrock Water Trucks.

Plugging Proposal Received by Carl
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30AM Day: 27 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Spot plug at 4275' w/4 sks common cement on plug

w/bailer. Shots at 2670' and 1800'. Shot off at 1430' and recovered pipe. Squeezed 8 5/8"

w/225 sks cement blend w/500# hulls mixed in to max psi 250#. Close in 150# psi. Plug complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

INVOICED

DATE 12-4-89

INV. NO. 26545

Gib.S

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

10-27 15-109-20099-00-00
API NUMBER 13-1978

NE NE, SEC. 7, T 12

4620 feet from _____
660 feet from _____

Lease Name Bertrand

County Logan

Well Total Depth 4750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 296

RECEIVED
NOV 20 1989
11-20-1989
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
154.38