

To: 6030471
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Operator: Chief Drly Co. Inc.
Name & Address: 905 Century Plaza
Wichita, Kansas
67202

API NUMBER 15-109-20,081-00-00

SUSE, SEC. 6, T 12 S, R 33 (W)

660 feet from S section line

1980 feet from E section line

Loose Name Johnston Well # 1

County Logan 156.00

Well Total Depth 4800' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 3/8 feet 285

Abandoned Oil Well X Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase Kansas

Company to plug at: Hour: AM Day: 5 Month: 6 Year: 19 85

Plugging proposal received from Ronnie

(company name) Kelso Casing (phone) _____

were: 8 3/8 set @ 285 w/ 1800 ft. 4 1/2 set @ 4798 w/ 2500 ft. Prof. 4330-38'

Order Com. Cam. Sand for bottom shoot and recover pipe Order

1800 ft 50/50 gel 6 3/4 gal 3 1/2 cc 8 3/8 W.P. 4 xphulls. Sun Cam. Wellbore
water truck.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:46 AM Day: 5 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT With bailer spot 4 x Com. Cam. on bottom. Dump sand
to 4280 - w/ bailer spot 4 x Com. Cam. on sand. Shoot and pull pipe.
2043' of 4 1/2 Recovered. Pump Down 8 3/8 w/ 3 xphulls + 2000 ft gel. - 1000 ft
Com. mix. 11 xphulls - 2000 ft gel. Release 8 3/8 W.P. - 800 ft. Recovered.
max P.S.I. 400⁺ Close in 150⁺ plug Complete.

STATE CORPORATION COMMISSION

JUN 24 1985

06-24-1985
CONSERVATION DIVISION

Remarks: _____
(If additional description is necessary, use BACK of this form)

INVOICED (If not observe this plugging.)

Signed Carl Goodnow
(TECHNICIAN)

24
6-21-85
mjs

DATE 6-26-85
INV. NO. 8722