

R!

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20684-00-00
Spot: SESESE Sec/Twp/Rge: 14-12S-33W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: VOTH INVESTMENT Well Number: 1
County: LOGAN Total Vertical Depth: 4720 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 219
Production: Size feet:
Liner: Size feet: \$153.40

Well Type: DH UIC Docket No: Date/Time to Plug: 06/17/2001 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BILL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 6% gel - 1/4# flocele per sack.
RTD 4720'. No arbuckle cut.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 06/17/2001 3:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

No Arbuckle cut.
1st. Plug at 2610' w/25 sxs. Middle of Anhydrite - 2600' - 2620'.
2nd. Plug at 1550' w/100 sxs. Dakota Base.
3rd. Plug at 269' w/40 sxs. Base surface pipe plus 50'.
4th. Plug at 40' w/10 sxs - with 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.
Total 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

INVOICED
DATE 7-06-01
INV. NO. 2002060024

RECEIVED
KANSAS CORPORATION COMMISSION
07-06-2001
JUL 6 2001
CONSERVATION DIVISION

Remarks:

Plugged through: DP

District: 04

101

Signed Richard Williams
(TECHNICIAN)

JUN 29 2001