

\$143.-

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23658-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 36-16S-22W  
330 feet from N Section Line, 990 feet from W Section Line  
Lease Name: UMMEL RANCH Well #: 2  
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	255		WITH 150 SX CMT
DVT		1894		WITH 325 SX CMT
PROD	5.5	4399	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2010 10:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES Phone: (620) 793-2146

Proposed  
Plugging  
Method:

PUMP 50 SX CMT & 200# HULLS. GEL SPACER TO 1900' CMT TO SURFACE. 50 SX FOR ANNULUS.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/17/2010 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

PUMPED 50 SX CMT & 200# HULLS. PUMP 12 SX GEL SPACER & 175 SX CMT.  
PRESSURE TO 300#. WENT ON VACUUM. TIED ONTO BACKSIDE & PUMPED 25 SX  
CMT. PRESSURED TO 500#. WAITED 30 MINUTES & TOPPED OFF CASING WITH 25  
SX CMT. STAYED FULL.

6/01/10  
2010061159

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED

MAY 19 2010

KCC DODGE CITY

Signed

(TECHNICIAN)

Form 2-26