

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22256-00-00 \$140.89
Spot: W2SESENE Sec/Twnshp/Rge: 29-17S-22W
2310 feet from N Section Line, 440 feet from E Section Line
Lease Name: FREIDENBERGER Well #: 1
County: NESS Total Vertical Depth: 4335 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	248		WITH 190 SX CMT
PROD	4.5	4332	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2010 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES Phone: (620) 793-2146

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS & 4 SX CMT THEN TEST CASING FOR LEAKS. IF NO LEAKS PLUG AT 1520' WITH 15 SX GEL & 50 SX CMT. PLUG AT 780' WITH 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2010 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 4200' WITH 4 SX CMT. PRESSURED CASING TO 300# & HELD. PULLED STRETCH ON CASING, COULDN'T PULL ENOUGH. PERFORATED CASING @ 800' & PUMPED 130 SX CMT. PRESSURED TO 700#. SHUT IN WITH 700#. TIED ONTO BACKSIDE & PUMPED 65 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4260	4265		

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED

MAY 24 2010

KCC DODGE CITY

Signed

Michael J. Maier
(TECHNICIAN)

Form CP 2/3