

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21257-00-00

Spot: NWNW

Sec/Twnshp/Rge: 31-33S-19W

\$ 175.50

660 feet from N Section Line,

660 feet from W Section Line

Lease Name: GIRK TRUST

Well #: 7

County: COMANCHE

Total Vertical Depth: 5400 feet

Operator License No.: 4058

Op Name: AMERICAN WARRIOR, INC.

Address: PO BOX 399

GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5150		WITH 2 SX CMT
SURF	8.625	674		WITH 475 SX CMT
PROD	4.5	5397	3023	WITH 150 SX CMT

Well Type: OG

UIC Docket No:

Date/Time to Plug: 05/14/2010 9:30 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: KEVIN WILES, SR

Company: AMERICAN WARRIOR

Phone: (620) 275-2963

Proposed
Plugging
Method:

CIBP @ 5150' WITH 2 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/14/2010 1:15 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5150' WITH 2 SX CMT. 1ST PLUG AT 1200', CIRCULATED MUD & PUMPED 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5238	5344		
5231	5234		
5202	5216		

6/01/10
2010061160

RECEIVED

MAY 24 2010

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Eric MacLaren

(TECHNICIAN)

RECEIVED

MAY 17 2010

KCC DODGE CITY

FOUR CR 21