

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23174-00-00 # 118.37  
Spot: S2NWNW Sec/Twnshp/Rge: 16-7S-20W  
4290 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: RISELEY B Well #: 3  
County: ROOKS Total Vertical Depth: 3642 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	257	0	160 SX
PROD	4.5	3631	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2010 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PRODUCTION Phone: (785) 302-1435

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Alt II 1710' w/350 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/10/2010 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2004'. Allied pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1500'. Allied pumped 100 sxs cement with 100#hulls.  
Pulled to 900'. Allied pumped 50 sxs cement with 150# hulls.  
PTOH. Topped 4 1/2" casing with 30 sxs cement. Casing full.  
Braden head 2" outlet - broke.  
05/13/2010 - Pat Bedore - Topped 4 1/2" with 10 sxs cement - casing full.  
Backside pumped 5 sxs.  
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3632	3642		
3382	3384		

6/01/10  
2010061161

RECEIVED  
MAY 24 2010  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN) CM

MAY 20 2010

STATE: KANSAS COUNTY: ROOKS 16-7S-20W  
FIELD: LESAGE E FLD (MULTIPAY) S2 NW NW  
OPER: ALCONA OIL 4290 FSL 4620 FEL SEC  
WELL: 3 RISELEY B WELL CLASS: DO ELEV: 2179 KB  
API: 15-163-23174 STATUS: OIL 2174 GR  
SPUD: 07/17/91 COMP: 07/22/91  
DTD: 3645 LTD: 3642 FTD: ARBUCKLE PBDT:

LOC: 9 MI N DAMAR, KS

IP: COMP 7/22/91, IPP 8 BOPD, 2 BWPD, GTY 28 PROD ZONE- TORONTO 3382-3384  
ARBUCKLE 3632-3645 OPENHOLE COMMINGLED  
NO CORES, ONE DST

LOG TOPS:

ANHYDRITE	1720 459	LANSING-KANSAS CITY	3397 -1218
TOPEKA	3151 -972	SIMPSON	3617 -1438
HEEBNER	3359 -1180	ARBUCKLE	3629 -1450
TORONTO	3381 -1202		
TD	3645 -1466		

LOG TYPES NOT RPTD  
CSGS: 8 5/8 @ 257 W/160 SX, 4 1/2 @ 3631 W/125 SX; TBG: 2 3/8 @ 3639; DRLG COMP  
07/21/91 RIG REL 07/22/91

(OVER)

COPYRIGHT 1991 PETROLEUM INFORMATION CORPORATION

DATE 11/08/91 CARD #00002-KS

STATE: KANSAS COUNTY: ROOKS 16-7S-20W  
FIELD: LESAGE E FLD (MULTIPAY) S2 NW NW  
OPER: ALCONA OIL 4290 FSL 4620 FEL SEC  
WELL: 3 RISELEY B WELL CLASS: DO  
(CONTINUED)

DSTS: DST # 1 (ARBUCKLE) 3635-3645, OP 30 MIN, SI 45 MIN, OP 30 MIN, SI 45 MIN,  
REC: 595 FT OIL, 40 FT MW, (595 FT FREE OIL) IFP 96, FFP 153, IFP 192, FFP 211,  
ISIP 586, FSIP 519, IHP 1882;  
PERFS: PERF (TORONTO) 3382-3384 W/5 PF, (ARBUCKLE) 3632-3645 OPENHOLE , ACID  
W/1000 GALS, 15% ACID W/750 GALS,  
PRODUCING INTERVAL: PERF (TORONTO) 3382-3384,(ARBUCKLE) 3632-3645  
OPENHOLE ,

OPER ADD: 2908 HILLCREST DR, HAYS, KS, 67601 PHONE (913) 628-2899;  
CONTR: MURFIN DRLG  
GEOL: LES LESAGE

COPYRIGHT 1991 PETROLEUM INFORMATION CORPORATION

DATE 11/08/91 CARD #00002-KS